

表A.0.2-5 总 预 算 表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

编制 范 围：忠县复兴镇2024年第二批农村公路护栏安装工程

第 1 页

共 1 页

01 表

分项编号	工程或费用名称	单位	数量	金额(元)	技术经济指标	各项费用比例 (%)	备 注
	第100章至700章清单			1221808		100.00	
	清单 第100章 总则			27470		2.25	
101	通则			9555		0.78	
101-1	保险费			9555		0.78	
-a	按合同条款规定, 提供建筑工程一切险	总额	1.000	5972	5972.00	0.49	1194338*0.5%
-b	按合同条款规定, 提供第三者责任险	总额	1.000	3583	3583.00	0.29	1194338*0.3%
102	工程管理			17915		1.47	
102-3	安全生产费	总额	1.000	17915	17915.00	1.47	1194338*1.5%
	清单 第600章 安全设施及预埋管线			1194338		97.75	
602	护栏			1194338		97.75	
602-3	波形梁钢护栏			1194338		97.75	
-a	路侧波形梁钢护栏	m	6596.000	1194338	181.07	97.75	
	已包含在清单合计中的材料、工程设备、专业工程暂估价合计						
	清单合计减去材料、工程设备、专业工程暂估价合计			1221808		100.00	
	计日工合计						
	劳务						
	材料						
	机械						
	暂列金额(不计日工总额)						
	投标报价			1221808		100.00	

编制:

复核:

表A.0.2-4 总预算人工、主要材料、施工机械台班数量汇总表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

第 1 页 共 1 页

02-1 表

代号	规格名称	单 位	总数量	编 制 范 围				
				忠县复兴镇2024年第二批农村公路护栏安装工程				
1001001	人工	工日	422.382	422.382				
1051001	机械工	工日	65.085	65.085				
2001019	钢丝绳	t	0.733	0.733				
2003005	钢板	t	1.619	1.619				
2003015	钢管立柱	t	65.417	65.417				
2003017	波形钢板	t	92.527	92.527				
2009011	电焊条	kg	310.891	310.891				
2009013	螺栓	kg	4901.189	4901.189				
3003002	汽油	kg	671.147	671.147				
3005002	电	kW·h	3050.041	3050.041				
3005004	水	m ³	79.152	79.152				
5503005	中(粗)砂	m ³	37.253	37.253				
5505015	碎石(8cm)	m ³	55.721	55.721				
5509001	32.5级水泥	t	19.160	19.160				
7801001	其他材料费	元	587.117	587.117				
8007001	2t以内载货汽车	台班	23.965	23.965				
8007003	4t以内载货汽车	台班	5.497	5.497				
8015028	32kV·A以内交流电弧焊机	台班	35.623	35.623				
8099001	小型机具使用费	元	3367.988	3367.988				

编制：

复核：

建筑安装工程费计算表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

编制范围：忠县复兴镇2024年第二批农村公路护栏安装工程

第 1 页 共 2 页

03-1 表

序号	分项编号	工程名称	单位	工程数量	定额直接费(元)	定额设备购置费(元)	直接费(元)				设备购置费	措施费	企业管理费	规费	利润(元)	税金(元)	金额合计(元)	
							人工费	材料费	施工机械使用费	合计					费率	税率	合计	单价
															7.42(%)	9(%)		
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
1		清单 第100章 总则															27470	
2	101	通则															9555	
3	101-1	保险费															9555	
4	-a	按合同条款规定,提供建筑工程一切险	总额	1.000	5972					5972							5972	5972.00
5	-b	按合同条款规定,提供第三者责任险	总额	1.000	3583					3583							3583	3583.00
6	102	工程管理															17915	
7	102-3	安全生产费	总额	1.000	17915					17915							17915	17915.00
8		清单 第600章 安全设施及预埋管线															1194338	
9	602	护栏															1194338	
10	602-3	波形梁钢护栏															1194338	
11	-a	路侧波形梁钢护栏	m	6596.000	953681		42661	907635	20712	971008		5583	27889	18019	73247	98617	1194338	181.07
12	5-1-2-3	波形钢板护栏立柱钢管柱打入	1t	64.769	393359		30092	357642	18061	405795		2219	11388	13216	30197	41653	504468	7788.73
13	5-1-2-5	波形钢板护栏单面	1t	91.611	536219		2776	530793	2651	536220		3024	15524	1219	41164	53744	650895	7104.99

编制：

复核：

建筑安装工程费计算表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

编制范围：忠县复兴镇2024年第二批农村公路护栏安装工程

序 号	分项 编号	工程名称	单位	工程 量	定额 直接 费 (元)	定额 设备 购置费 (元)	直接费(元)				设备 购置费	措施费	企业 管理费	规费	利润	税金	金额合计	
							人工费	材料费	施工机械 使用费	合计					(元)	(元)	(元)	
															费率 7.42(%)	税率 9(%)	合计	单价
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
		波形钢板																
14	5-1-2 -1	波形钢板护栏基础 混凝土	10m3 实体	6.596	24103		9793	19200		28993		340	977	3584	1886	3220	39000	5912.67
合 计					981151	0	42661	907635	20712	998478	0	5583	27889	18019	73247	98617	1221808	0.00

编制：

复核：

表A.0.2-9 综合费计算表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

编制范围：忠县复兴镇2024年第二批农村公路护栏安装工程

第 1 页

共 1 页

04-1 表

序号	工程名称	措施费										企业管理费						规 费						
		冬季 施工 增加 费	雨季 施工 增加 费	夜间 施工 增加 费	高原 地区 施工 增加 费	风沙 地区 施工 增加 费	沿海 地区 施工 增加 费	行车 干扰 施工 增加 费	施工 辅助 费	工地 转移 费	综合 费用		基本 费用	主副 食 运费 补贴	职工 探亲 路费	职工 取暖 补贴	财务 费用	综合 费用	养老 保险 费	失业 保险 费	医疗 保险 费	工伤 保险 费	住房 公积 金	综合 费用
		I	II																					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
1	路侧波形梁钢护栏		51						5532		51	5532	21706				6182	27888	7878	246	4923	788	4185	18020
				</																				

表A.0.2-14 人工、材料、施工机械台班单价汇总表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

编制范围：忠县复兴镇2024年第二批农村公路护栏安装工程

第 1 页 共 1 页

09 表

序号	名称	单位	代号	预算单价(元)	备注	序号	名称	单位	代号	预算单价(元)	备注
1	人工	工日	1001001	101.00							
2	机械工	工日	1051001	101.00							
3	钢丝绳	t	2001019	5970.09							
4	钢板	t	2003005	5300.00							
5	钢管立柱	t	2003015	5300.00							
6	波形钢板	t	2003017	5300.00							
7	电焊条	kg	2009011	5.73							
8	螺栓	kg	2009013	7.35							
9	汽油	kg	3003002	8.80							
10	电	kW·h	3005002	0.85							
11	水	m ³	3005004	3.50							
12	中(粗)砂	m ³	5503005	180.00							
13	碎石(8cm)	m ³	5505015	90.00							
14	32.5级水泥	t	5509001	390.00							
15	其他材料费	元	7801001	1.00							
16	2t以内载货汽车	台班	8007001	347.10							
17	4t以内载货汽车	台班	8007003	482.31							
18	32kV·A以内交流电弧焊机	台班	8015028	178.95							
19	小型机具使用费	元	8099001	1.00							

编制：

复核：

表A.0.3-1 分项工程预算计算数据表

建设项目名称：忠县复兴镇2024年第二批农村公路护栏安装工程

编制范围：忠县复兴镇2024年第二批农村公路护栏安装工程

标准定额库版本号：

校验码：

第 1 页 共 1 页

21-1 表

分项编号/ 定额代号/ 工料机代号	项目、定额 或工料机的名称	单位	数量	输入单价	输入金额	分项组价 类型或 定额子目 取费类别	定额调整情况或分项算式
	第100章至700章清单				1221808		
	清单 第100章 总则				27470		
101	通则				9555		
101-1	保险费				9555		
-a	按合同条款规定，提供建筑工程一切险	总额	1.000	5972.00	5972		
-b	按合同条款规定，提供第三者责任险	总额	1.000	3583.00	3583		
102	工程管理				17915		
102-3	安全生产费	总额	1.000	17915.00	17915		
	清单 第600章 安全设施及预埋管线				1194338		
602	护栏				1194338		
602-3	波形梁钢护栏				1194338		
-a	路侧波形梁钢护栏	m	6596.000	181.07	1194338		
5-1-2-3	波形钢板护栏立柱钢管柱打入	1t	64.769	7788.73	504468	13	
5-1-2-5	波形钢板护栏单面波形钢板	1t	91.611	7104.99	650895	13	
5-1-2-1	波形钢板护栏基础混凝土	10m3实体	6.596	5912.67	39000	6	

编制：

复核：